

CITY OF NORTHGLENN

**2022 CONNECT NORTHGLENN MULTIMODAL STREETS
IFB 2022-033**

ADDENDUM NO. 1

DATED: April 4, 2023

TO: PROSPECTIVE BIDDERS

The following adds to, supplements, amends or clarifies by way of explanation, portions of the Contract Documents, Specifications, and Drawings for the above named project.

NOTE: It will be the responsibility of the Bidder to acknowledge receipt of Addenda on the Bid Form as part of his/her submitted proposal. Failure to do so will be grounds for the City to reject the proposal.

The Contract Documents, including the Specifications and Drawings are hereby modified by the following items:

QUESTIONS:

We have the following questions regarding the above referenced project:

Q1. The plan sheets show a count of 14 RRFBs, the Summary of Approx. Quantities has 12 RRFBs and the Bid Summary in the IFB has 10 RRFBs, which quantity is correct?

A1. A total of 12 RRFBs are to be installed for this project. A new Bid Summary is provided.

Q2. Bid Summary shows RRFBs on the Leroy Dr – Larson Dr to Irma Dr, but they are not shown on the plans, where will these be placed?

A2. No RRFBs will be installed along Leroy Dr.

Q3. On the plans sheets 29, 36 & 40 show RRFBs on Truda, Acoma and Kennedy (sheet titled Acoma), but these are not shown on the Bid Summary. Which is correct and will a revised Bid Summary be provided to match?

A3. Sheets 36 and 37 shall be removed from the drawing set. RRFBs on Truda (Sheet 29) and Kennedy (Sheet 40) will remain in place. A new Bid Summary is provided.

Q4. Will Pedestrian push buttons be needed to go with the RRFBs?

A4. Yes. Refer to Sheet Number 10, Note 3 and Front Elevation View.

Q5. Will all signs shown on sheet 10 of the plan be required?

A5. Yes.

Q6. Are precast pedestal foundations all right or will the foundations need to be pour in place?

A6. *No, cast in place foundations are required for all RRFBs. Refer to Sheet Number 8, Note 3.*

City of Northglenn
Eric Czaikowski
Civil Engineer II

Attachments: Revised Bid Summary 4/4/2023

ALL ITEMS IN CONFLICT WITH THIS ADDENDUM ARE HEREBY DELETED.

END OF ADDENDUM NO 1

Revised Bid Summary 4/4/2023

Vendor: TBD

Hereby submits to the City of Northglenn, Colorado the following bid items complete and in place as specified for the:
2022 Connect Northglenn Multimodal Improvements - IFB 2022-033

Item No.		Description	Quantity	Unit	Unit Cost	Total Cost
1	626-00000	Mobilization & Demobilization	1	LS		
Leroy Dr - Larson Dr to Irma Dr						
2	630-80380	Traffic Cone	75	EA		
3	630-80341	Construction Traffic Sign	8	EA		
4	627-00002	Preformed Thermoplastic Pavement Marking (Bike Lane)	792	SF		
5	627-00004	Epoxy Pavement Marking (4")	24,750	LF		
Total Leroy Dr - Larson Dr to Irma Dr						\$ -
115th Ave - Irma Dr to Claude Ct						
6	630-80380	Traffic Cone	75	EA		
7	630-80341	Construction Traffic Sign	8	EA		
8	627-00002	Preformed Thermoplastic Pavement Marking (Bike Lane)	504	SF		
9	627-30210	Preformed Thermoplastic Pavement Marking (X-Walk & Stopline)	126	SF		
10	627-00004	Epoxy Pavement Marking (4")	10,000	LF		
11	614-80003	Solar Rapid Rectangular Flashing Beacon	2	EA		
Total 115th Ave - Irma Dr to Claude Ct						\$ -
E 112th Pl						
12	630-80380	Traffic Cone	75	EA		
13	630-80341	Construction Traffic Sign	8	EA		
14	614-80003	Solar Rapid Rectangular Flashing Beacon	2	EA		
Total E 112th Pl						\$ -
Phillips Dr - Washington St to Claude Ct						
15	630-80380	Traffic Cone	75	EA		
16	630-80341	Construction Traffic Sign	8	EA		
17	627-00002	Preformed Thermoplastic Pavement Marking (Bike Lane)	1,080	SF		
18	627-30210	Preformed Thermoplastic Pavement Marking (X-Walk & Stopline)	558	SF		
19	627-00004	Epoxy Pavement Marking (4")	26,000	LF		
20	614-80003	Solar Rapid Rectangular Flashing Beacon	2	EA		
Total Phillips Dr - Washington St to Claude Ct						\$ -
Truda Dr - Sylvia Dr to Claude Ct						
21	614-80003	Solar Rapid Rectangular Flashing Beacon	2	EA		\$ -
Total Truda Dr - Sylvia Dr to Claude Ct						\$ -
Kennedy Dr - Claire St to Acoma St						
22	630-80380	Traffic Cone	75	EA		
23	630-80341	Construction Traffic Sign	8	EA		
24	627-00002	Preformed Thermoplastic Pavement Marking (Bike Lane)	1,260	SF		

25	627-30210	Preformed Thermoplastic Pavement Marking (X-Walk & Stopline)	324	SF		
26	627-00004	Epoxy Pavement Marking (4")	38,750	LF		
27	614-80003	Solar Rapid Rectangular Flashing Beacon	2	EA		
Total Kennedy Dr - Claire St to Acoma St						\$ -
Fox Run Parkway - 104th Ave to 112th Ave						
28	630-80380	Traffic Cone	75	EA		
29	630-80341	Construction Traffic Sign	8	EA		
30	627-00002	Preformed Thermoplastic Pavement Marking (Bike Lane)	1,260	SF		
31	627-00004	Epoxy Pavement Marking (4")	34,450	LF		
32	627-30210	Preformed Thermoplastic Pavement Marking (X-Walk & Stopline)	918	SF		
33	614-80003	Solar Rapid Rectangular Flashing Beacon	2	EA		
Total Fox Run Parkway - 104th Ave to 112th Ave						\$ -
					Total	\$ -